

GENERAL SUMMARY

Prepared for:

Project ID:

Scope:

DRYWALL, METAL FRAME,
INSULATION

No. Of Floors:

1


Date:

22-Nov-23



BUILDING GSF 11474
1st Floor (SF) 11474

DIVISION NO	DESCRIPTION	TOTAL DIV. COST	TOTAL DIV. COST (PER SF)
1000	General Requirements	\$ 51,500	\$ 4.49
5000	Metals	\$ 72,902	\$ 6.35
6000	Wood & Plastics	\$ 14,421	\$ 1.26
7000	Thermal & Moisture Protection	\$ 87,859	\$ 7.66
9000	Finishes	\$ 125,140	\$ 10.91
TOTAL TRADE COST		\$ 351,822	\$ 31
OVERHEAD AND PROFIT	15%	\$ 52,773	\$ 4.60
LABOUR BURDEN	22%	\$ 32,226	
INSURANCE	3%	\$ 10,555	\$ 1
CONTINGENCY	5%	\$ 17,591	\$ 2
TAX	6%	\$ 9,231	\$ 2
SUGGESTED BID		\$ 474,198	\$ 40



Total Labor cost of project	\$ 146,480
Labor per Sft	\$ 12.77

DETAILED BREAKDOWN OF ITEMS														
Prepared for: Project ID: Scope: DRYWALL, METAL FRAME, INSULATION														
														
												Date:	\$ 45,252	
Drawing #	SR #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST	
GENERAL REQUIREMENTS														
1			Permits	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ -	\$ -	
2			Supervision and Coordination	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 20,000.00	\$ 20,000	
3			Submittals and Shop drawings	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 6,500.00	\$ 6,500	
4			Final Cleaning	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 3,000.00	\$ 3,000	
5			Mobilization Costs	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 16,500.00	\$ 16,500	
6			Temporary Control & Facilities	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 4,000.00	\$ 4,000	
7			Scaffolding	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 1,500.00	\$ 1,500	
												SUBTOTAL	\$ 51,500	
METALS														
			DRYWALL ASSEMBLIES											
	A2, A3 & A5		6" Interior Metal Stud Wall (18'-4" H.)	LF	136									
8			6" 18 GA. Metal Studs @ 16"O.C	SF	2493	10%	2742	0.014	\$ 65.00	\$ 0.91	\$ 1.62	\$ 2.53	\$ 6,938	
9			6" 18 GA. Top Runner	LF	136	10%	150	0.018	\$ 65.00	\$ 1.17	\$ 2.15	\$ 3.32	\$ 497	
10			6" 18 GA. Bottom Runner	LF	136	10%	150	0.018	\$ 65.00	\$ 1.17	\$ 2.15	\$ 3.32	\$ 497	
				6" Interior Metal Stud Wall (18'-0" H.)	LF	675								
11				6" 18 GA. Metal Studs @ 16"O.C	SF	12150	10%	13365	0.014	\$ 65.00	\$ 0.91	\$ 1.62	\$ 2.53	\$ 33,813
12				6" 18 GA. Top Runner	LF	675	10%	743	0.018	\$ 65.00	\$ 1.17	\$ 2.15	\$ 3.32	\$ 2,465
13				6" 18 GA. Bottom Runner	LF	675	10%	743	0.018	\$ 65.00	\$ 1.17	\$ 2.15	\$ 3.32	\$ 2,465
				3-5/8" Interior Metal Stud Wall (9'-6" H.)	LF	16								
14				3-5/8" 25 GA. Metal Studs @ 16"O.C	SF	152	10%	167	0.014	\$ 65.00	\$ 0.91	\$ 1.46	\$ 2.37	\$ 396
15				3-5/8" 25 GA. Top Runner	LF	16	10%	18	0.018	\$ 65.00	\$ 1.17	\$ 1.95	\$ 3.12	\$ 55
16				3-5/8" 25 GA. Bottom Runner	LF	16	10%	18	0.018	\$ 65.00	\$ 1.17	\$ 1.95	\$ 3.12	\$ 55
				Metal Stud Plumbing Wall (9'-6" H.)	LF	8								
17				3-5/8" 25 GA. Metal Studs @ 16"O.C	SF	152	10%	167	0.014	\$ 65.00	\$ 0.91	\$ 1.46	\$ 2.37	\$ 396
18				3-5/8" 25 GA. Top Runner	LF	16	10%	18	0.018	\$ 65.00	\$ 1.17	\$ 1.95	\$ 3.12	\$ 55
19				3-5/8" 25 GA. Bottom Runner	LF	16	10%	18	0.018	\$ 65.00	\$ 1.17	\$ 1.95	\$ 3.12	\$ 55
				6" Exterior Metal Stud Wall (17'-0" H.)	LF	303								
20				6" 18 GA. Metal Studs @ 16"O.C	SF	5151	10%	5666	0.014	\$ 65.00	\$ 0.91	\$ 1.62	\$ 2.53	\$ 14,335
21				6" 18 GA. Top Runner	LF	303	10%	333	0.018	\$ 65.00	\$ 1.17	\$ 2.15	\$ 3.32	\$ 1,107
22				6" 18 GA. Bottom Runner	LF	303	10%	333	0.018	\$ 65.00	\$ 1.17	\$ 2.15	\$ 3.32	\$ 1,107
			6" Exterior Metal Stud Wall (18'-0" H.)	LF	151									
23			6" 18 GA. Metal Studs @ 16"O.C	SF	2718	10%	2990	0.014	\$ 65.00	\$ 0.91	\$ 1.62	\$ 2.53	\$ 7,564	
24			6" 18 GA. Top Runner	LF	151	10%	166	0.018	\$ 65.00	\$ 1.17	\$ 2.15	\$ 3.32	\$ 551	
25			6" 18 GA. Bottom Runner	LF	151	10%	166	0.018	\$ 65.00	\$ 1.17	\$ 2.15	\$ 3.32	\$ 551	
												SUBTOTAL	\$ 72,902	
WOOD & PLASTICS														
			DRYWALL ASSEMBLIES											
			6" Exterior Metal Stud Wall (17'-0" H.)	LF	303									
26			5/8" Plywood Sheathing	SF	5151	10%	5666	0.008	\$ 65.00	\$ 0.55	\$ 1.12	\$ 1.67	\$ 9,440	

Labor Cost	Mat. Cost
\$ -	\$ -
\$ -	\$ -
\$ 2,495.37	\$ 4,442.31
\$ 175.03	\$ 321.64
\$ 175.03	\$ 321.64
\$ -	\$ -
\$ -	\$ -
\$ 12,162.15	\$ 21,651.30
\$ 868.73	\$ 1,596.38
\$ 868.73	\$ 1,596.38
\$ -	\$ -
\$ -	\$ -
\$ 152.15	\$ 244.11
\$ 20.59	\$ 34.32
\$ 20.59	\$ 34.32
\$ -	\$ -
\$ -	\$ -
\$ 152.15	\$ 244.11
\$ 20.59	\$ 34.32
\$ 20.59	\$ 34.32
\$ -	\$ -
\$ -	\$ -
\$ 5,156.15	\$ 9,179.08
\$ 389.96	\$ 716.60
\$ 389.96	\$ 716.60
\$ -	\$ -
\$ -	\$ -
\$ 2,720.72	\$ 4,843.48
\$ 194.34	\$ 357.12
\$ 194.34	\$ 357.12
\$ -	\$ -
\$ -	\$ -
\$ -	\$ -
\$ 3,093.69	\$ 6,346.03

	A2, A3 & A5												
			6" Exterior Metal Stud Wall (18'-0" H.)	LF	151								
27			5/8" Plywood Sheathing	SF	2718	10%	2990	0.008	\$ 65.00	\$ 0.55	\$ 1.12	\$ 1.67	\$ 4,981
												SUBTOTAL	\$ 14,421
THERMAL & MOISTURE PROTECTION													
DRYWALL ASSEMBLIES													
			6" Interior Metal Stud Wall (18'-4" H.)	LF	136								
28			R-19 Batt Insulation	SF	2493	10%	2742	0.008	\$ 65.00	\$ 0.52	\$ 1.02	\$ 1.54	\$ 4,223
29			Sealant	SF	544	10%	598	0.010	\$ 65.00	\$ 0.65	\$ 0.25	\$ 0.90	\$ 539
			6" Interior Metal Stud Wall (18'-0" H.)	LF	675								
30			R-19 Batt Insulation	SF	12150	10%	13365	0.008	\$ 65.00	\$ 0.52	\$ 1.02	\$ 1.54	\$ 20,582
31			Sealant	SF	2700	10%	2970	0.010	\$ 65.00	\$ 0.65	\$ 0.25	\$ 0.90	\$ 2,673
			3-5/8" Interior Metal Stud Wall (9'-6" H.)	LF	16								
32			3-1/2" R-19 Sound Batt Insulation	SF	152	10%	167	0.008	\$ 65.00	\$ 0.52	\$ 1.02	\$ 1.54	\$ 257
33			Sealant	SF	64	10%	70	0.010	\$ 65.00	\$ 0.65	\$ 0.25	\$ 0.90	\$ 63
			Metal Stud Plumbing Wall (9'-6" H.)	LF	8								
34			3-1/2" R-19 Sound Batt Insulation	SF	152	10%	167	0.008	\$ 65.00	\$ 0.52	\$ 1.02	\$ 1.54	\$ 257
35			Sealant	SF	32	10%	35	0.010	\$ 65.00	\$ 0.65	\$ 0.25	\$ 0.90	\$ 32
			6" Exterior Metal Stud Wall (17'-0" H.)	LF	303								
36			6" R-19 Sound Batt Insulation	SF	5151	10%	5666	0.014	\$ 65.00	\$ 0.91	\$ 1.36	\$ 2.27	\$ 12,862
37			Sealant	SF	606	10%	667	0.010	\$ 65.00	\$ 0.65	\$ 0.25	\$ 0.90	\$ 600
			6" Exterior Metal Stud Wall (18'-0" H.)	LF	151								
38			6" R-19 Sound Batt Insulation	SF	2718	10%	2990	0.014	\$ 65.00	\$ 0.91	\$ 1.36	\$ 2.27	\$ 6,787
39			Sealant	SF	302	10%	332	0.010	\$ 65.00	\$ 0.65	\$ 0.25	\$ 0.90	\$ 299
			CEILING INSULATION										
40			R-30 Ceiling Insulation	SF	12427	10%	13670	0.018	\$ 65.00	\$ 1.17	\$ 1.66	\$ 2.83	\$ 38,685
												SUBTOTAL	\$ 87,859
FINISHES													
DRYWALL ASSEMBLIES													
			6" Interior Metal Stud Wall (18'-4" H.)	LF	136								
41			5/8" Gypsum Wall Board	SF	4986	10%	5484	0.015	\$ 65.00	\$ 0.98	\$ 0.62	\$ 1.60	\$ 8,748
			6" Interior Metal Stud Wall (18'-0" H.)	LF	675								
42			5/8" Gypsum Wall Board	SF	24300	10%	26730	0.015	\$ 65.00	\$ 0.98	\$ 0.62	\$ 1.60	\$ 42,634
			3-5/8" Interior Metal Stud Wall (9'-6" H.)	LF	16								
43			5/8" Gypsum Wall Board	SF	304	10%	334	0.015	\$ 65.00	\$ 0.98	\$ 0.62	\$ 1.60	\$ 533
			Metal Stud Plumbing Wall (9'-6" H.)	LF	8								
44			5/8" Gypsum Wall Board	SF	152	10%	167	0.015	\$ 65.00	\$ 0.98	\$ 0.62	\$ 1.60	\$ 267
			6" Exterior Metal Stud Wall (17'-0" H.)	LF	303								
45			5/8" Gypsum Wall Board	SF	5151	10%	5666	0.015	\$ 65.00	\$ 0.98	\$ 0.62	\$ 1.60	\$ 9,037
			6" Exterior Metal Stud Wall (18'-0" H.)	LF	151								
46			5/8" Gypsum Wall Board	SF	2718	10%	2990	0.015	\$ 65.00	\$ 0.98	\$ 0.62	\$ 1.60	\$ 4,769
			CEILING										
47			5/8" Gypsum Board Ceiling	SF	11715	10%	12886	0.018	\$ 65.00	\$ 1.17	\$ 0.62	\$ 1.79	\$ 23,066

\$ -	\$ -
\$ -	\$ -
\$ 1,632.43	\$ 3,348.58
\$ -	\$ -
\$ -	\$ -
\$ -	\$ -
\$ -	\$ -
\$ -	\$ -
\$ -	\$ -
\$ 1,425.93	\$ 2,797.01
\$ 388.96	\$ 149.60
\$ -	\$ -
\$ -	\$ -
\$ 6,949.80	\$ 13,632.30
\$ 1,930.50	\$ 742.50
\$ -	\$ -
\$ -	\$ -
\$ 86.94	\$ 170.54
\$ 45.76	\$ 17.60
\$ -	\$ -
\$ -	\$ -
\$ 86.94	\$ 170.54
\$ 22.88	\$ 8.80
\$ -	\$ -
\$ -	\$ -
\$ 5,156.15	\$ 7,705.90
\$ 433.29	\$ 166.65
\$ -	\$ -
\$ -	\$ -
\$ 2,720.72	\$ 4,066.13
\$ 215.93	\$ 83.05
\$ -	\$ -
\$ -	\$ -
\$ 15,993.33	\$ 22,691.39
\$ -	\$ -
\$ -	\$ -
\$ -	\$ -
\$ -	\$ -
\$ 5,347.23	\$ 3,400.29
\$ -	\$ -
\$ -	\$ -
\$ 26,061.75	\$ 16,572.60
\$ -	\$ -
\$ -	\$ -
\$ -	\$ -
\$ 326.04	\$ 207.33
\$ -	\$ -
\$ -	\$ -
\$ 163.02	\$ 103.66
\$ -	\$ -
\$ -	\$ -
\$ 5,524.45	\$ 3,512.98
\$ -	\$ -
\$ -	\$ -
\$ 2,915.06	\$ 1,853.68
\$ -	\$ -
\$ -	\$ -
\$ 15,076.90	\$ 7,989.47

		Note: We Have Considered Gypsum Board Ceiling In All Tenant Places. Please Confirm & Verify										
		TAPPING, MUDING & SCREWS										
48		Taping	LF	24663	10%	27129	0.005	\$ 65.00	\$ 0.33	\$ 0.10	\$ 0.43	\$ 11,530
49		Mudding	LBs.	2614	10%	2876	0.085	\$ 65.00	\$ 5.53	\$ 0.75	\$ 6.28	\$ 18,045
50		Screws	EA	73988	10%	81387				\$ 0.08	\$ 0.08	\$ 6,511
SUBTOTAL											\$	125,140
PROJECTED COST											\$	351,822
OVERHEAD AND PROFIT											15%	\$ 52,773
LABOUR BURDEN											22%	\$ 32,226
INSURANCE											3%	\$ 10,555
CONTINGENCY											5%	\$ 17,591
TAX											6%	\$ 9,231
SUGGESTED BID											\$	474,198

\$	-	\$	-
\$	-	\$	-
\$	-	\$	-
\$	8,816.94	\$	2,712.90
\$	15,888.12	\$	2,156.76
\$	-	\$	6,510.97
\$	146,479.92	\$	153,842.38